BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41803

APPROVED SCHEDULE - B

.E/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

.me of Work:Filling of Pot Holes at Doddabommsandra area in ward No 10 Doddabommsandra idyaranyapura sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of A BALAJI ( )	
				In Figures	In Words
1	214.22	KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	1701.09	Rupees One Thousand Seven Hundred One and Nine Paise Only
2	1429.12	KSRRB 3000 Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications	Sqm	275.71	Rupees Two Hundred Seventy Five and Seventy One Paise Only

Signature of the Contractor

14/08

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

14/08